


9

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Harvey County, Sec. 30 Twp. 22S Rge. 3W (R) (W)
Location as "NE/CNW/SW" or footage from lines C N/2 N/2 NW/4
Lease Owner Aladdin Petroleum Corporation
Lease Name Franz Well No. 1
Office Address 809 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil and disposal
Date well completed September 20 1964
Application for plugging filed September 9 1965
Application for plugging approved September 13 1965
Plugging commenced September 10 1965
Plugging completed September 12 1965
Reason for abandonment of well or producing formation not profitable

If a producing well is abandoned, date of last production August 19 65
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman 3646
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3664 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	506	none
				5-1/2	3626	2566

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3664 to 3300 sand.
3300 to 3270 5 sacks cement.
Pulled 2566' of 5-1/2" pipe.
Set plug at 300'.
Rock wedge 300' to 280'.
20 sacks cement 280 to 220.
mud to 30'.
10 sacks cement to base of cellar.

9-24-65

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1965

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Ellin Wood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Jerome M. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerome M. Johnson
Jerome M. Johnson

809 Petroleum Buldg, Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 22nd day of September 19 65

My commission expires September 19, 1967

Esther L. Marshall
Esther L. Marshall Notary Public.

15-079-30000-0000
9

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Aladdin Petroleum Corporation
FARM Franz NO. 1

SEC. 30 T. 22 R. 3 W
LOC. 0-N/2-N/2-W

TOTAL DEPTH 3634'
COMM. 9/4/64 COMP. 9/20/64
SHOT OR TREATED
CONTRACTOR O'Rourke-Jones Drilling Company, Inc.
ISSUED

COUNTY Harvey
KANSAS

CASING
20 10
15 8 -5/8" @ 506' w/450 BX
12 6
13 5 -1/2" @ 3626' w/150 BX

ELEVATION 1448 KB
1443 GL
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 0 - 40 Clay and sand
- 50 Shale
- 75 Sand
- 350 Shale and sand
- 507 Shale and shells
- 540 Shale
- 625 Shale and shells
- 1215 Shale and lime
- 1545 Shale and shells
- 2250 Shale and lime
- 2360 Sand
- 2420 Lime and shale
- 2540 Lime
- 2595 Lime and shale
- 2686 Lime
- 2745 Lime and shale
- 2830 Lime
- 2885 Lime and shale
- 2980 Lime
- 3130 Lime and shale
- 3182 Chert
- 3251 Lime and chert
- 3514 Lime and shale
- 3530 Lime
- 3555 Lime and iron
- 3571 Lime, sand, shale
- 3588 Limey shale and chert
- 3606 Simpson sand
- 3634 Lime and sand

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1965
CONSERVATION DIVISION
Wichita, Kansas

Total depth - 3634'

I, Robert L. Jones of O'Rourke-Jones Drilling Company, Inc., do hereby certify that the above and foregoing are true according to the records of the company.

O'Rourke-Jones Drilling Company, Inc.

By Robert L. Jones