

9


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Harvey County, Sec. 30 Twp. 22 Rge. 3 ~~XXXX~~ (W)
Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Kantor Oil Company
Lease Name Katie Schmidt Well No. 8
Office Address 2001 Philtower Bldg., Tulsa, Okla - 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed November 22, 1968
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced November 22, 1968
Plugging completed November 22, 1968
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott, McPherson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3393 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0	35	13"	35'	None
Sand		35	100	13"	65'	Mpme
Shale		100	200	13"	100'	None
Sand		200	240	13"	40'	None
Blue Shale		240	311	13"	71'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 300 ft., set plug and put in 35 sacks cement. Filled with mud to 40 ft. set plug and 15 sacks cement. 2 sacks in rathole. Plugging job completed by Hugh Scott, State Pluggger of McPherson, Kansas on November 22, 1968 at 10:00 A.M.....

12-2-68

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.
Address Box # 455, McPherson, Kansas - 67460

STATE OF OKLAHOMA, COUNTY OF Tulsa, ss.
Joe Kantor (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. KANTOR OIL COMPANY


(Signature) _____ by: [Signature]
2001 Philtower Bldg., Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 1968

My commission expires 10-1-69

Colleen White

Notary Public.



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON • KANSAS

67460

November 22, 1968

COMPANY: KANTOR OIL COMPANY
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: SCHMIDT # 8
 LOCATION: C-W/2 NW/4 NE/4, Sec. 30-22-3W, Harvey County, Kansas
 COMMENCED: November 14, 1968
 COMPLETED: November 22, 1968
 ELEVATION:

0	to	35	Clay
35	to	100	Sand
100	to	200	Shale
200	to	240	Sand
240	to	311	Blue Shale
311	to	1265	Lime & Shale
1265	to	1995	Shale & Lime
1995	to	2380	Lime
2380	to	2500	Lime & Shale
2500	to	2956	Lime
2956	to	3115	Lime & Shale
3115	to	3190	Shale & Lime
3190	to	3230	Lime
3230	to	3240	Shale
3240	to	3345	Shale & Lime
3345	to	3383	Lime & Shale
		3383	T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 2 1968
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 15 1/4 in. hole to 311 ft. and run 313.60 ft. of 13 in. and cemented with 275 sacks on bottom at 311 ft. Plug down at 4:00 pm, Nov. 15, 1968. Cut 7 7/8 in. hole to 3383 ft. Mixed 40 hbbls. oil in mud. Hole dry and abandoned. Filled hole with mud to 300 ft. set plug and put in 35 sacks cement. Filled with mud to 40 ft. set plug with 15 sacks cement. 2 sacks in rathole. Plugging job completed by Hugh Scott, State Plugger of McPherson, Kansas on November 22, 1968 at 10:00 a.m.

TOPS: Lansing - 2414' Cherokee - 3030' Mississippi - 3112' Kinderhook - 3230'
 Misner - 3334' Hunton - 3340' Maquoketa - 3348'

Measurements taken from K.S.

CERTIFICATE

I, H. J. Plouffe, president of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Katie Schmidt #8, located on the C-W/2 NW NE, Sec. 30-22-3W, Harvey County, Kansas as reflected by the files of BLACKSTONE DRILLING, INC.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 22nd day of November, 1968.

Ruth McVay
 Ruth McVay - Notary Public

