

KANSAS  
STATE CORPORATION COMMISSION

15-009-19099-8300

CONSERVATION DIVISION AGENT'S REPORT  
STATE CORPORATION COMMISSION

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

OCT 4 1961  
10-04-61  
CONSERVATION DIVISION  
Wichita, Kansas

File No. \_\_\_\_\_ County: Barton

Location: SW NW NE Sec. 1 Twp. 16 Rge. 12W (E) (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3400

I have this date completed supervision of plugging of:

Lease Name: Woydziak "A" Well No. 1

Operator's Full Name: Birmingham-Bartlett Drilling Co.

Complete Address: 300 Kaufman Bldg., Wichita, Kansas

Plugging Contractor Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

if yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 11:30 AM Day 27 Month 9 Year 1961

The above well was plugged as follows:

Set bottom plug @ 3310' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mudded hole to 330', set rock bridge, & dumped 4 sax

cement on bridge with dump bailer. Let set over-night. Bailed hole

dry & dumped 20 sax cement.. Mud to 40', set rock bridge, & dumped

10 sax cement, cementing to base of cellar.

Signed: Don Truman  
Conservation Division Agent

Reviewed: Harold Holis  
Field Supervisor

Remarks:

INVOICED

DATE 10/13/61

INV. NO. 3840-11