

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten mark]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-185-12762-0000

FILE NO. 43-1

LOCATION SE-SE-SE

SEC. 28 TWP. 23 RGE. 13-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease J. B. O'Conner

Operator Fawcett Oil & Gas Co Address Box #7 Ellinwood-Kans.

Field _____ County Stafford

Total Depth 3930 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 307 ft. Pipe isolated with cement
5 1/2 casing set at 3926 ft. Cemented with 10 sacks cement.
Plugged back to 3920 ft with chat - Pumped 5 sacks of
cement at 3920 ft. Shot off & Pulled the 5/8 casing.
Mud to 300 ft. Set Rock Bridge & 15 sacks of cement
at 300 ft. Mud to 30 ft. Plug & 10 sacks of
cement at the surface

Jack Walker - Plugging Contractor

STATE CORPORATION COMMISSION

JAN 15 1951 1-15-51

CONSERVATION DIVISION

C. K. [Signature]
District Conservation Agent

Date 1-13-51

PLUGGING
FILE SEC 21 T 23 R 13W
BOOK PAGE 42 LINE 1