

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

Crown Oil moved into an old hole
formerly drilled by Helmerich
& Payne
FILE NO. 15-185-00879-0001
LOCATION SE SE SE
SEC. 29 TWP. 25 RGE. 15 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Zimmerman
Operator Crown Oil Co Address 2477 Center St. Great Bend, Kans
Field _____ County Stafford
Total Depth 4040 Feet.

(Describe briefly the manner in which the well was plugged)
10" at 365', circulated with cement - 5 1/2" at 3850' with
250 Sax behind- lane wells plugs to 5575' - Perforations at
3545' - Chat to 5535 and 5 sax cement - Heavy mud to 565',
wood plug and 20 sax cement - Heavy mud to 50', woodplug
rock and 10 sax cement .

RECEIVED

Conservation Div. 6-20-49

JUN 20 1949

STATE CORPORATION COMMISSION

Edna
District Conservation Agent

Date 6-18-49

PLUGGING
FILE SEC 29 T 25 R 15 W
BOOK PAGE 102 LINE 4