

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Harvey County, Sec. 30 Twp. 23 Rge. 3 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW

Lease Owner Raymond Law & Larry Moore Ranch, Inc.

Lease Name Franz Well No. 1

Office Address McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Aug. 19 19 54

Application for plugging filed Aug. 23 19 54

Application for plugging approved Aug. 23 19 54

Plugging commenced August 23 19 54

Plugging completed August 25 19 54

Reason for abandonment of well or producing formation No oil & too much water

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation None Depth to top Bottom Total Depth of Well 3490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	315'	None
				5-1/2"	3258'	2738'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The cement was not drilled out inside the pipe. Cement filled to 3228' and casing was perforated from 3173' to 3181'. Filled hole with sand from 3228' to 3160' and ran 6 sacks of cement. Mudded hole to 305', set a rock bridge to 290', bailed fluid from hole and ran 15 sacks of cement at 290'. Mudded hole to 25', set a 10' rock bridge and ran 5 sacks of cement on top. Plugging compl.

RECEIVED  
CONSERVATION DIVISION  
9-9-54  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.  
Ray Law (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ray Law

(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of Sept. 19 54

Carnell D. Winkler  
Notary Public.

My commission expires Jan. 17, 19 57

PLUGGING  
FILE SEC 30 T 22 R 3W  
BOOK PAGE 60 LINE 10

COMPANY: R. Law & Larry Moore Ranch Inc.  
 CONTRACTOR: Mallard Drilling Company  
 FARM: Franz #1  
 LOCATION: S/2 NE NW Sec. 30-225-3W  
 Harvey County, Kansas  
 COMMENCED: July 30, 1954  
 COMPLETED: August 8, 1954

0	to	45	Shale
45	to	180	Sand
180	to	205	Shale and red bed
205	to	240	Sand
240	to	315	Shale
315	to	324	Shale
324	to	500	Lime
500	to	670	Lime
670	to	1105	Lime
1105	to	1450	Shale
1450	to	1912	Shale and lime
1912	to	1995	Lime
1995	to	2125	Lime and shale
2125	to	2255	Lime
2255	to	2440	Shale and lime
2440	to	2550	Lime
2550	to	2765	Lime
2765	to	2930	Lime
2930	to	3159	Lime and shale
3159	to	3170	Lime and chert
3170	to	3205	Misc. Lime
3205	to	3245	Lime and chert
3245	to	3255	Shale and lime
3255	to	3265	Lime and chert
3265	to	3300	Lime, shale and chert
3300	to	3310	Lime
3310	to	3380	Shale
3380	to	3422	Shale
3422	to	3490	Lime
		3490	T.D.

Set 324 feet of 8 5/8" surface pipe. Cemented with 200 sacks cement.  
 Set 5 1/2" at 3258. Cemented with 75 sacks cement.  
 TOPS: Mississippi -- 3163

Measurements taken from R.D.B. B.D.G. 5 1/2' from ground level.

STATE \_\_\_\_\_

C E R T I F I C A T E COMMERCIAL ENGINEER

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Franz #1, Harvey County, Kansas, as reflected by files of the Mallard Drilling Company.

*C. C. Nelson*

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 17th day of August 1954.

*James W. [Signature]*

My commission expires 12/4/56

**PLUGGING**  
 FILE SEC 30 T 22 R 3W  
 BOOK PAGE 40 LINE 10