


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
~~WELL PLUGGING RECORD~~
OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission,
800 Bitting Building,
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Harvey County. Sec. 30 Twp. 22 Rge. (E) 3 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NE NE
Lease Owner W. C. McBride, Inc.,
Lease Name Abr. Schmidt Well No. 3
Office Address 1226 Olive Street, St. Louis, Mo.
Character of Well (Completed as Oil, Gas or Dry Hole) Oil Well
Date, well completed July 6, 1933 193
Application for plugging filed September 15, 1939 193
Application for plugging approved September 16, 1939 193
Plugging Commenced September 21, 1939 193
Plugging Completed October 2, 1939 193
Reason for abandonment of well or producing formation Production so small it did not pay to operate
If a producing well is abandoned, date of last production September 3, 1939.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Wilcox Sand Depth to top 3542 Bottom 3561 Total Depth of Well 3561 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi Lime (Chat)	Dry	3165	3230	15 1/2"	333'	None
Hunton Lime	Show Oil	3387 1/2	3410	8-5/8"	3373'	2252' 6"
Viola Lime	Dry	3519	3540	7"	3516' 3"	3516' 3"
Wilcox	Oil	3542	3561			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud dumped in hole from 3561 to 3550 and cement from 3550 to 3525 - cement dumped with bailer. Mud dumped from 3525 to 3100' and cement from 3100 to 3082 - cement dumped with bailer. Hole bridged at 2500' with wood plug and rock and dumped six sacks cement with bailer. Hole bridged at 335' with plug and rock and cemented with 20 sacks of cement. Hole filled to bottom of cellar with mud and capped with 10 sacks of cement at top of hole in bottom of cellar.

FILE SEC 30-22-30
BOOK PAGE 76 LINE 5

(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to W. C. McBride, Inc.,
Address Box 433, McPherson, Kansas.

STATE OF KANSAS, COUNTY OF McPHERSON, ss.
Frank Zimmerman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Zimmerman

Box 433, McPherson, Kansas.

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1939.

Filed 10-7-39

David Paoli

My commission expires July 15, 1943.

Notary Public.

FORMATION RECORD, Cont'd.

Depth from	To	Feet	Formation
	1425		shale & shells
	1640		shale
	1727		broken lime & shale
	1789		broken lime
	1796		lime
	1819		broken lime & shale
	1880		shale
	1950		broken lime & shale
	2005		broken lime
	2270		lime
	2297		shale & sand
	2367		sand & lime shells
	2402		broken lime
	2475		lime
	2486		broken sand
	2500		lime
	2515		broken lime
	2570		lime
	2576		broken sand
	2689		lime
	2697		sand
	2823		lime
	2843		broken lime
	2868		lime & broken shale
	2983		shale
	2893		broken lime
	2903		lime
	2918		broken lime
	2945		slatey shale
	2979		broken lime
	2993		lime
	3016		lime & shale
	3034		lime
	3067		lime & shale
	3107		shale & lime shells
	3124		shale
	3165		shale & lime shells
	3190		Chat
	3219		Chat & shale
	3243		lime
	3265		Chat & lime
	3299		lime
	3312		broken lime & shale
	3365		shale
	3385		shale & lime
	3393		black shale
	SLC 3393=3373		
	3381		Lime - show bil
	3410		Lime
	3513		Shale & lime
	3515		shale, grayish green
	3542		lime, green shale & sand
	3559		Sand
	3561 T.D.		Sand

W. C. McBRIDE, Inc.
Grand Building
McPHERSON, KAS.

October 6, 1939.

MAIN OFFICE
1228 Olive Street
ST. LOUIS, MO.

Kansas State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas.

Attention: Mr. T. A. Morgan, Director.

Dear Sir:

We are enclosing herewith Well Plugging Record of our Schmidt well #3 located in Section 30-22S-3W, Harvey County, Kansas, Hollow Nikkel Pool.

Please forward a supply of the enclosed forms as our present supply has exhausted.

Daffin

Yours very truly,

W. C. McBride, Inc.,

By *[Signature]*
Frank Zimmerman.

DP

*forms sent
10/7/39
H.A.*

PLUGGING
FILE SEC 30-22-3W
BOOK PAGE 76 LINE 5