


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 9 Twp. 22 Rge. 11 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SE/4 NE/4 NW/4  
Lease Owner Republic Natural Gas Company  
Lease Name Fair "D" Well No. 1  
Office Address Box 126, Ellinwood, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed May 27 19 56  
Application for plugging filed June 26 19 56  
Application for plugging approved June 27 19 56  
Plugging commenced August 13 19 56  
Plugging completed August 17 19 56  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3554 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	182'	None
				7"	3553'	2778'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Baker bridge plug set at 3250'  
Run sand from 3250' to 3222'.  
Dumped 6 sacks cement at 3222'.  
Pulled casing.  
Pumped in 20 sacks mud and 120 sacks cement.

8-25-56  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1956  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
P. B. Horst (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. B. Horst  
Box 126, Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of August, 19 56

Helen Mae Berscheidt  
Notary Public.

My commission expires 8-30-59

PLUGGING  
FILE SEC. 9 T. 22 R. 11 W  
BOOK PAGE 74 LINE 26

DRILLER'S LOG

Company: Republic Natural Gas Company  
 Lease and Well: Fair D-1  
 Location: SE/4 NE/4 NW/4 Section 9-22S-11W  
 County: Stafford  
 Contractor: H & H Drilling Company  
 Commenced: May 6, 1954  
 Completed: May 27, 1954

0 - 20	Sand and clay
20 - 182	Red bed and shale
182 - 480	Shale
480 - 1150	Shale and shells
1150 - 1355	Shale
1355 - 1425	Lime and shale streaks
1425 - 1575	Lime and shale
1575 - 1750	Shale and lime
1750 - 1850	Lime
1850 - 1945	Lime and shale
1945 - 2800	Shale and lime
2800 - 2941	Lime and shale
2941 - 3434	Lime
3434 - 3494	Conglomerate
3494 - 3517	Simpson
3517 - 3554	Arbuckle
3554	T.D.

Casing Record: 10-3/4" surface casing set at 182' cemented with 150 sacks.

7" production casing set at 3553' cemented with 100 sacks.

**PLUGGING**

FILE SEC. 9 T. 22 R. 11W  
 BOOK PAGE 74 LINE 36