


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 9 Twp. 22S Rge. 11 W/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW NE
Lease Owner Mustang Drilling & Exploration, Inc.
Lease Name Sara Sleeper Well No. 1
Office Address P.O. Drawer 1609, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole)



Dry Hole
Date Well completed November 2 1981
Application for plugging filed November 2 1981
Application for plugging approved November 2 1981
Plugging commenced November 2 1981
Plugging completed November 2 1981
Reason for abandonment of well or producing formation

D & A
If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well J.H. Metz, Stafford, Ks.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	400	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

500' 60 sx
240' 40 sx
40' 10 sx
Rathole 10 sx
120 sx 50=50 poz
3% cc; 2% gel

11-4-81
RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mustang Drilling & Exploration, Inc.

STATE OF Kansas COUNTY OF Barton, ss.
Kenneth Roach (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth O. Roach
P.O. Drawer 1609, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 81

STATE NOTARY PUBLIC
BEVERLY SHEWBART
Barton County, Kansas
My Appt. Exp. April 14, 1982

Beverly Shewbart
Notary Public.

My commission expires

DRILLERS' WELL LOG

OPERATOR: Mustang Drilling & Exploration, Inc.
P.O. Drawer 1609, Great Bend, Kansas 67530

WELL: Sara Sleeper #1 API # 15- 185-21,379

LOCATION: c SW NE
Sec 9 -T 22 S-R 11W

COMMENCED: 10-25-81 COMPLETED: 11-2-81

ELEVATION: GL: 1752 DF: KB: 1757 TOTAL DEPTH: 3650

CASING: Surface: 8 5/8"; 24 #; set at 400 feet;
Cemented with 250 sacks Common cement; 3% cc; 2% gel.

Production: ; #; set at feet;
Cemented with sacks cement;

DEPTH:	FORMATION	FORMATION TOPS	
0 - 400	Shale, Red bed	Topeka	2701
400 - 1665	Shale	Heebner	3000
1665 - 2701	Lime, Shale	Toronto	3019
2701 - 3000	Lime	Douglas	3035
3000 - 3004	Shale	Brown Lime	3139
3004 - 3035	Lime	Lansing	3168
3035 - 3139	Shale	Base KC	3416
3139 - 3168	Lime, Shale	Conglomerate	3430
3168 - 3416	Lime	Conglomerate	
3416 - 3430	Lime, Shale	Sand	3452
3430 - 3452	Lime, Shale, Sand, Chert	Viola	3552
3452 - 3552	Sand	Simpson Sand	3571
3552 - 3571	Lime	Simpson Shale	3582
3571 - 3582	Sand	Arbuckle	3620
3582 - 3620	Shale	LTD	3650
3620 - 3650	Dolomite	RTD	3650
3650	LTD		
3650	RTD		

ACKNOWLEDGEMENT

STATE OF KANSAS, COUNTY OF BARTON, ss:

Before me, the undersigned, a Notary Public, within said county and state, on this 3rd day of November personally appeared Kenneth Roach to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary deed for the uses and purposes therein set forth.

Subscribed and sworn to before me this 3rd day of November, 1981.

My Appointment Expires April 1, 1987
BEVERLY SHEWBART
Notary Public
My App. Exp. 4-1-87

Kenneth Roach
Beverly Shewbart
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1981
Conservation Division
Wichita, Kansas