

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas. 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 11-9-65

LEASE NAME Fair

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

Approx. 4950 Ft. from S Section Line

Approx. 4290 Ft. from E Section Line

LEASE OPERATOR Rains & Williamson Oil Co. Inc.

SEC. 9 TWP. 22 RGE. 11 (W)

ADDRESS 435 Page Court 220 West Douglas, Wichita, Kan.

COUNTY Stafford

PHONE# (316) 265-9686 OPERATORS LICENSE NO. 5146

Date Well Completed 11-9-65

Character of Well Oil

Plugging Commenced 7-18-86

Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-18-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Kansas City Depth to Top 3297 Bottom 3344 T.D. 3495

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Kansas City</u>	<u>Oil</u>	<u>3297</u>	<u>3344</u>	<u>5 1/2</u>	<u>3494</u>	<u>1759</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

B-S Titan Pumped down hole 3 sk. hulls followed by 10sk gel. and 50sk 60/40 psz mix cement followed by 5sk gel and 1sk hulls. Released 8 3/4 plug followed with 100 sk 60/40 psz mix cement with 6 1/2 gel. Max. press 700 lbs. Shut in at 500 lbs.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Paul Stephens License No. 683

Address P.O. Box 166

STATE OF Kansas COUNTY OF Pratt, ss.

Rains & Williamson Oil Co. Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Stephens

(Address) \_\_\_\_\_

RECEIVED

SUBSCRIBED AND SWORN TO before me this 6<sup>th</sup> day of August, 19 86

8-8-86

Mary Alice Rupp  
Notary Public

My Commission Expires: 2-29-88

AUG 8 1986

Mary Alice Rupp  
NOTARY PUBLIC  
State of Kansas  
MY APT. EXPIRES 2-29-88