

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,717-0000

LEASE NAME Eriksen

WELL NUMBER 4

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 9 TWP. 22S RGE. 11 (E) or (W)

COUNTY STAFFORD

Date Well Completed 9-27-90

Plugging Commenced 9-27-90

Plugging Completed 9-27-90

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, Kansas 67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 27, 1990 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3612'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0'	287'	8 5/8"	287'	none

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

50 sx. @ 550', 50 sx. @ 320', 10 sx @ 40' w/solid bridge, 15 sx. in rathole
Total 125 sx. 60/40 Pozmic, 6% CEI

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Great Bend, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc. Great Bend, Ks.

STATE OF KANSAS COUNTY OF BARTON, ss.


Greg Davidson (Employee of Operator) or (~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) Great Bend, Kansas 67530

10-22-90

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1990



(Signature) Bessie M. DeWerff
Notary Public

My Commission Expires 5-20-93

Bessie M. DeWerff

KCC

DRILLER'S WELL LOG

OCT 22 1990

COMMENCED: 9-22-90
 COMPLETED: 9-27-90

0- 287 Surface
 287- 310 Red Bed
 310- 1040 Red Bed & Shale
 1040-2535 Shale & Lime
 2535-3612 Lime & Shale
 3612 RTD

L.D. Drilling, Inc;
 Eriksen #4
 SW NE SW Sec. 9-22S-11W
 Stafford County, Kansas

ELEVATION: 1786' Ground 1791' KB

FORMATION DATA: (Samples)

Anhy.	464-489
Heebner	3036 (-1245)
Toronto	3058 (-1267)
Douglas	3072 (-1281)
Brown Lime	3173 (-1382)
Lansing	3197 (-1406)
Base K/C	3445 (-1645)
Cong.	3464 (-1673)
RTD	3612 (-1821)

SURFACE CASING:

8 5/8" set @ 287' W/165 sx.
 60/40 Pozmix, 2% Gel, 3% CC


AFFIDAVIT

STATE OF KANSAS)
 CPIMTU OF BARTON) ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
 Greg Davidson

Subscribed and sworn to before me this 22nd day of October, 1990



Bessie M. DeWerff
 Bessie M. DeWerff: Notary Public

My Commission expires: 5-20-93