

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER (Comp.) 4-17-63

LEASE NAME E.P. Ward SWDS

WELL NUMBER 4
760' Ft. from S Section Line

560' Ft. from E Section Line
of SW/4
SEC. 16 TWP. 22S RGE. 33W (E) or (W)

COUNTY Finney

Date Well Completed 4-17-63

Plugging Commenced 11-22-88

Plugging Completed 11-22-88

JAN 27 1989
1-27-89
CONSERVATION DIVISION
Wichita, Kansas

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texaco Inc.

ADDRESS P.O. Box 2420

PHONE# (918) 560-6000 OPERATORS LICENSE NO. _____

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 18, 1988 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Glorietta Sand Depth to Top 1540' Bottom 1640' T.D. 1710'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Glorietta Sand	SWD			7"	33'	None
		1540'	1640'	4-1 1/2"	1709'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Set bridge plug at 1444'. Cemented 4 1/2" casing from 1444' to 5' w/100 sx cement, 65/35 poz w/6% gel. Cut off casing 5' below ground level, welded on steel plate, filled w/native dirt and cleaned and leveled location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texaco, Inc. License No. _____

Address P.O. Box 2420

STATE OF Oklahoma COUNTY OF Tulsa, ss.

John K. Hamby (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John K. Hamby
District Commission Engineer

(Address) _____

SUBSCRIBED AND SWORN TO before me this 18th day of January, 19 89

Deborah M. Colburn
Notary Public

My Commission Expires: 8-3-92