


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Finney County, Sec. 16 Twp. 22S Rge. 33 (EX) (W)
Location as "NE/CNW&SW" or footage from lines SW-SW
Lease Owner Texaco Inc.
Lease Name E. P. Ward Well No. 5
Office Address P. O. Box 2420
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 6/22/72 19
Application for plugging filed 6/15/72 19
Application for plugging approved 6/16/72 19
Plugging commenced 6/22/72 19
Plugging completed 6/22/72 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4847 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	457'	none
				4 1/2"	4846'	2296'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Shot csg @ 2503'. Could not pull. Shot @ 2285' & pld 2296' 4 1/2"-10.5#
8 rd-Rg 2 J55 csg. PB from 4813 to 4500' w/20 sx cmt, 4500-2260' w/hvy mud, 2260-2174' w/25 sx 50/50 poz, 2174-507' w/hvy mud, 507-407' w/35 sx 50/50 poz, 407-52' w/hvy mud, 52-3' w/15 sx 50/50 poz, 3' to surface w/dirt.

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Toland & Johnson
Address 1315 S.E. 29th St., Oklahoma City, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
F.E. ANDERSON, Asst. Dist. Supt. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. E. Anderson*
P. O. Box 2420, Tulsa, Okla.
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1972


My commission expires 8/10/74

Notary Public

WELL LOG

COMPANY **Texaco, Inc.**
 FARM **E. P. Ward** NO. **5**
 TOTAL DEPTH **4847'**
 COMM. **5-17-72** COMP. **5-27-72**
 CONTRACTOR **Garvey Drilling Company**

SEC. **16** T. **22S** 33W
 LOC. **SW SW**
 COUNTY **Finney, Kansas**



CASINGS
8 5/8" @ 455' w/400sx
4 1/2" @ 4846' w/150sx
DV Tool @ 2806' w/125sx

ELEVATION
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 140' Clay & Sand
- 190' Shale
- 1275' Sand & Shale
- 1356' Shale
- 1376' Anhydrite
- 1745' Shale & Sand
- 2170' Shale & Lime
- 2810' Lime & Shale
- 3985' Shale & Lime
- 4071' Lime & Shale
- 4497' Lime
- 4847' Lime
- 4847' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 16 1972
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } SS

I, Charlene Marker of Garvey Drilling Company
 upon oath state the above and foregoing is a true and correct copy of the log of the E. P. Ward #5 well.

Charlene Marker

Subscribed and sworn to before me this 1st day of June 1972

My Commission Expires: July 8, 1974

Gene C. Morris
 NOTARY PUBLIC