


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
File or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Finney County. Sec 16 Twp. 22S Rge. 33 (W)
Location as "NE/CNW/SE/SW" or footage from lines Ctr NW SW
Lease Owner Texaco Inc.
Lease Name E. P. Ward Well No. 3
Office Address 614 Bitting Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 2-3-1960
Application for plugging filed 9-12-1968
Application for plugging approved 9-13-1968
Plugging commenced 12-3-1968
Plugging completed 12-4-1968
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 6-1-1964
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves
Producing formation Mississippi Depth to top 4700 Bottom 4728 Total Depth of Well 4850 Feet
Show depth and thickness of all water, oil and gas formations. 4740 PB

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil	4712	4728	8-5/8"	400'	None
				5-1/2"	4860'	1693'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: 4740-4700 w/sd, 4700-4660 w/5 sxs cmt, 4660-410 w/mud, 410-400 w/rock, 400-310 w/30 sxs cmt, 310-40 w/mud, 40-30 w/rock, 30-4 w/10 sxs cmt. Comp 6:30 PM 12-4-68.

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor McAdams Pipe & Supply
Address Box 960, Bristow, Oklahoma

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. E. Anderson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. E. Anderson
614 Bitting Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 17th day of December, 1968



Peggy Sue Jones
Notary Public.

My commission expires 10-13-69

Texaco, Inc.
Tulsa, Oklahoma

Tulsa, Oklahoma
January 18, 1960

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: December 17, 1959
Drilling Completed: January 8, 1960

E. P. Ward #3 NW SW Section
16-22S-33W, Finney County,
Kansas.

DRILLERS LOG

Depth Figures Indicate Base Of Formation:

Surface	0
Top Soil	70
Shale	100
Sand	150
Shale	411
Shale & Shells	1300
Shale- Red Bed & Shells	1880
Shale & Shells	2260
Shale & Lime	3032
Lime & Shale	3387
Shale & Lime	3770
Lime & Shale	4427
Core #1	4428
Core #2	4434
Lime	4435
Core #3	4457
Lime	4726
Core #4	4750
Lime	4765
Core #5	4823
Lime	4650 TD

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1968
CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete
Drillers Log of Texaco Inc., E. P. Ward #3, NW SW Section 16-22S-33W,
Finney County, Kansas.


Fred E. Stickle


Notary Public

My Commission Expires
January 8, 1964