

State of Kansas



15-185-12258-0001

FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

APR 27 1964
 4-27-64
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Howard Ward of Tommy Ward Drilling Co. has this

date requested permission to plug the following described well:

Mr. Ward guarantees payment of the plugging fee.

Operator's full Name: Woody's Quality Oil Company

Complete Address: 1119 Cravens Bldg., Oklahoma City, Oklahoma

Lease Name: Soeken "A" Well No. # 3

Location: SW NE SE Sec. 10 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3880 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ward was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cement circulated. Fill hole
with drilling mud to 245', 1st cementing plug, bridge with
hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent