

State of Kansas



15-185-30016-0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 22 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Howard Ward of Tommy Ward Drilling Co. has this date requested permission to plug the following described well:

Mr. Ward guarantees payment of the plugging fee.

Operator's full Name: Woody's Quality Oil Company

Complete Address: 1119 Cravens Bldg., Oklahoma City, Oklahoma

Lease Name: Soeken "A" Well No. # 2

Location: NE SE SE Sec. 10 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3875 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Ward was instructed to plug the well as follows:

395' of 8 5/8" surface pipe, cemented with 400 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent