

State of Kansas



15-185-13010-0000

FORM - CP-2

Q

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 1 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

10-1-63

Dear Sir:

Mr. Ralph Comstock of Comstock Pipe Pulling Inc has this date requested permission to plug the following described well:

Mr. Comstock guarantees payment of the plugging fee.

Operator's full Name: National Cooperative Refinery Assoc.

Complete Address: 305 Rule Bldg., Wichita, Kansas

Lease Name: Curtis "B" Well No. # 3

Location: C NW NW Sec. 6 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3610 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Comstock was instructed to plug the well as follows:

343' of 8 5/8" surface pipe, cemented with 250 sacks.

3609' of 5 1/2" long string, cemented with 125 sacks. Plug-

ged back to 3300', with Baker plug, cemented with 2 sacks.

Fill hole with mud to 300', 10' rock bridge, cement with

25 sacks. Fill hole with mud to 40', 10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent