

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

7-7-66
JUL 7 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-185-30263-0000

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sterling Drilling Company

Complete Address: Box 127, Sterling, Kansas

Lease Name Gray Well No. # 4

Location SE SW SW Sec. 18 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3680'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sterling Drilling Company

Address: Box 127, Sterling, Kansas License No.

Operation Completed: Hour 4:00AM Day July 1st Month July 1st Year 1966

The Above well was plugged as follows:

379' of 7" surface pipe, cement circulated with 160 sacks. 20 sacks of
cement was pumped on bottom at 3675', through the drill pipe. Fluid level
in the hole was at 94'. 1st cementing plug and 1/2 sack of hulls was pushed
in fluid to 300', and cemented with 20 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

This cementing was done by Halliburton Cementing Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-7-66

INV. NO. 3537-427