

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1971
CONSERVATION DIVISION
Wichita, Kansas

9-16-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sterling Drlg. Co. 15-185-16950-0000

Complete Address Box 129 Sterling Ks

Lease Name Gray Well No. 2

Location NW/SW/SW Sec. 18 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3990

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 3.PM Day 15 Month 9 Year 1971

The above well was plugged as follows:

368 ft 8 5/8 surface pipe cemented with 225 sacks. 3989 ft 5 1/2 long
string cemented with 150 sacks. Set plug at 3680 ft. Top perf. 3618
ft. Sand back to 3600 ft, 5 sacks cement with bailer. Pulled 2007 ft
5 1/2. Pump 2 sacks hulls, 16 sacks gel., 100 sacks cement to surface.

Pumped by Allied Cementing Co.

Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. Russell B. Hunter
Well Plugging Supervisor

DATE 9-16-71

INV. NO. 4335-W