

KANSAS

SL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sterling Drlg. Co. 15-185-00654-0000

Complete Address Box 129 Sterling, Ks

Lease Name Gray Well No. 1

Location SW/SW/SW Sec. 18 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3992

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 2:P M Day 15 Month 9 Year 1971

The above well was plugged as follows:

359 ft 8 5/8 surface pipe cemented with 225 sacks. 3783 ft 5 1/2 long
string cemented with 100 sacks. Top perf. 3620 ft. Sand back to
3600 ft, 5 sacks cement with bailer. Pulled 3004 ft 5 1/2. Pump 2 sacks
hulls, 15 sacks gel., 100 sacks cement to surface.

Pumped by Allied Cementing Co.

Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-16-71

INV. NO. 4334-W

Signed: *M. Russell B. Stewart*
Well Plugging Supervisor