

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-185-00821-0000

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1963

CONSERVATION DIVISION
Wichita, Kansas

11-12-53

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jay Kornfeld

Complete Address: 623 Union National Bldg., Wichita, Kansas

Lease Name Ben Schulz Well No. # 1

Location NE NE NW Sec. 20 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 4023

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 1:30PM Day 9th Month Nov. Year 1963

The Above well was plugged as follows:

316' of 8 5/8" surface pipe, cemented with 200 sacks. 3770' of 5 1/2" long
string, cemented with 75 sacks. Top perferation 3644'. Bottom of hole was
sanded to 3625', and cemented with 5 sacks. Fluid level was up in hole.
Plug was pushed to 275', bridged with 10' of rock. 4 sacks of cement was
mixed in barrel and put on plug, through dump bailer, and let set over
night. Next morning hole bailed down, and 21 sacks cement was added to plug.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar. 3218' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 11/12/63
INV. NO. 8073-11

Signed: Archie Elving
Well Plugging Supervisor