

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1966
3-31-66
Subscribed and sworn to before me
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc. 15-185-01399-0001

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Soden Well No. # 1

Location SE NE SE Sec. 23 Twp. 23 Rge. 13 (E) (W) W

County Stafford Total Depth 3800'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 10:30AM Day 28th Month March Year 1966

The Above well was plugged as follows:

265' of 8 5/8" surface pipe, cemented with 250 sacks. 3800' of 4 1/2" long
string, cemented with 125 sacks. Top perferation 3624'. Bottom of the hole
was sanded to 3600', and cemented with 3 sacks, through the dump bailer.
3240' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed
in fluid to 255', rock bridge from 255' to 245'. 6 sacks of cement was mixed
in a barrel, and put on plug at 245', through the dump bailer, and let set
over-night. Next day hole was bailed dry, and 19 sacks of cement was added
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/31/66
INV. NO. 2962-11