

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-20.561-0000

LEASE NAME Williams

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR General Oil Co., Inc.

SEC. 12 TWP. 22S RGE. 14W (E) or (W)

ADDRESS 1540 N. Broadway #202 Wichita, KS 67214

COUNTY Stafford

PHONE (316) 263-8588 OPERATORS LICENSE NO. 9069

Date Well Completed

Character of Well SWD

Plugging Commenced 10-14-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-14-96

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3830'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 350' | none |
| | | | | 4 1/2 | 3830' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each string. Ran 2 3/8" tubing to 3400'. Mixed 30 sx 60/40 poz 6% and 1 gel. Displace down to 2920'. pulled tubing to 2800'. Pumped 14 sx gel spacer. Displaced to 800'. Pulled tubing to 800'. Mix 225 sx 60/40 poz 6% gel and circulate up 4 1/2. Pulled tubing out. Put 4 1/2 swedge in. Mixed 65 sx 60/40 6%. Circulate good cement out 8 5/8 annulus. Shut in annulus. Mix 10 sx 60/40 6% 300# psi. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: General Oil Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 96

Jane Herzberg
 Notary Public

My Commission Expires:

RECEIVED
 KANSAS COMMISSION
 OCT 30 1996

