

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 10 S. Market, Room 207B  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-02-3-117

15-185-1223-00-00

API NUMBER Comp. 8-17-56

LEASE NAME Roach "A"

WELL NUMBER 3

4950 Ft. from S Section Line

990 Ft. from E. Section Line

SEC. 12 TWP. 22 RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-21-01

Plugging Completed 3-22-01

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS R.R. 1 Box 183B Great Bend, Kansas 67530

PHONE (316) 793-3051 OPERATORS LICENSE NO. 4656

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Peifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3714'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	364'	None
				5-1/2"	3709'	2315'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 3670' and 5 sk. cement, shot pipe @2700', 2500' and 2315', pulled up to 850', pumped 10 sks. gel and 50 sks. cement, pulled up to 390', pumped 50 sks. cement, pulled to 40' and filled to surface with 20 sks. cement. 60/40 pos. 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Davis Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss. 3-30-01

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of March, 2001

My Commission Expires: \_\_\_\_\_

