



ROACH-WILSON NO. 1 WELL

LOCATION: SW $\frac{1}{4}$  NE $\frac{1}{4}$  SE $\frac{1}{4}$  12-22S-11W  
Stafford County, Kansas

OPERATOR: Manhart-Millison & Beebe

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 10-3/4" casing cemented at 308'  
with 350 sacks cement and 4 c.c.

OIL STRING: None. D & A

SPEUDED: 5-27-52  
COMPLETED: 6-10-52

L O G

(Figures indicate bottom of formation)

0 to 300	Sand and Shells
313	Shale and Shells
500	Sand and Redbed
1710	Shale and Shells
1825	Lime
2065	Lime and Shale
2185	Shale and Shells
2490	Lime and Shale
2760	Shale and Shells
2830	Lime
2935	Lime and Shale
3310	Lime
3370	Shale and Sand
3425	Lime and Shale
3655	Lime
3700	Lime and Shale
3762	Shale
3787	Lime
3787	Total Depth.

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Roach-Wilson #1 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn before me  
this 11th day of June, 1952.

Vivian F. Genger  
Notary Public

My commission expires November 29, 1954.

RECEIVED  
CORPORATION COMMISSION  
JUN 21 1952  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE REC 17-2-1952  
BOOK PAGE 22 LINE 37

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- MANHART-MILLISON & BEEBE  
Form- Roach-Wilson No. 1

SEC. 12 T. 22 R. 14W  
S. 1 NE SE

Total Depth. 3787  
Comm. 5-27-52 Comp. 6-10-52  
Shot or Cased.  
Contractor. Birmingham-Bartlett Drlg. Co.  
Issued. 7-26-52

County Stafford  
KANSAS



CASING:

10 3/4" 308' cen. w/350 sx

Elevation. 1924

Production. Dry

Figures indicate Bottom of Formations.

sand & shells	300
shale & shells	313
sand & red bed	500
shale & shells	1710
lime	1825
lime & shale	2065
shale & shells	2185
lime & shale	2490
shale & shells	2760
lime	2830
lime & shale	2935
lime	3310
shale & sand	3370
lime & shale	3425
lime	3655
lime & shale	3700
shale	3762
lime	3787
Total Depth	

Elec. Log Tops:	
Anhydrite	788
Lansing	3412
Base-K. C.	3633
Viola	3682
Simpson	3702
Arbuckle	3757

RECEIVED  
STATE CORPORATION COMMISSION

NOV 11 1954

CONSERVATION DIVISION  
Wichita, Kansas