

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 12 Twp. 28 SRge. 14W(E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW NE

Lease Owner E. H. Riggs

Lease Name Wilson Well No. 1

Office Address 408 Rule Bldg. - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed January 1, 19 53

Application for plugging filed July 7 19 54

Application for plugging approved July 9 19 54


Plugging commenced July 16 19 54

Plugging completed July 21 19 54

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Merle Rives



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3764 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	351'	None
				5-1/2"	3731'	3207'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3764' to 3713' and ran 5 sacks of cement. Pumped in 25 sacks of mud at 1750'. Bailed mud down to 300', set a 10' rock bridge and ran 20 sacks of cement at 290'. Mudded hole to 35' and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

E. H. RIGGS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. H. Riggs

(Address) _____

SUBSCRIBED AND SWORN TO before me this 13 day of August, 1954

My commission expires March 3, 1958

Gene L. Murrain Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 12 T 22 R 14W
BOX PAGE 47 LINE 2

HONAKER DRILLING COMPANY
2008 LAKIN
GREAT BEND, KANSAS

DRILLER'S LOG

COMPANY: Honaker Drilling Co., et al
CONTRACTOR: Honaker Drilling Co.

Total Depth: 3735'
Comm: 12-27-52
Comp: 1-9-53

FARM: Wilson #1
Sec: 12-228-14W
Loc: NE SW 30
Stafford County, Kansas

Elevation: 1027 H.D.
Casing: 8 5/8" 351'
8 1/2" 3731'

0	10	Top Soil
10	325	Sand
325	352	Red Bed & Shale
352	430	Sand & Shale
430	650	Shale & Shells
650	785	Red Bed
785	825	Anhydrite
825	1020	Red Bed & Shells
1020	1300	Shale & Shells
1300	1370	Shale & Lime
1370	1665	Shale & Shells
1665	1815	Lime & Shale
1815	1930	Lime
1930	2005	Lime & Shale
2005	2125	Lime
2125	2200	Lime & Shale
2200	2710	Shale & Lime
2710	2800	Shale
2800	3180	Shale & Lime
3180	3295	Lime
3295	3398	Shale & Lime
3398	3735	Lime
3735		Total Rotary Depth

8 5/8" casing cemented at 351 ft. with 225 sacks cement.

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

Subscribed and sworn to before me this _____ day of _____ 1953.

PLUGGING
FILE SEC 12 T 22 R 14W
BOOK PAGE 47 LINE 2

My Commission Expires: June 25, 1955.

5 1/2" set at 3731' - Cemented w/ 70 REEF Cement
Total Coker tool depth 3764'
40' 4 1/2" Linner - top at 3713'

STATE CORPORATION COMMISSION
AUG 26 1954
CONSERVATION DIVISION
Wichita, Kansas