

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-12911-0001

LEASE NAME Drach #1

WELL NUMBER No. 1

SPOT LOCATION C/W2 SW SE

SEC. 11 TWP. 22 RGE. 13 (SE) or (W)

COUNTY Stafford

Date Well Completed 7-7-53

Plugging Commenced 10-15-84

Plugging Completed 10-15-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Stalcup Oil Company

ADDRESS 3511 - 23rd Great Bend, Kansas 67530

PHONE # (316) 793-3118 OPERATORS LICENSE NO. 7702

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Office (Steve Durant)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation Kansas City Depth to top _____ bottom _____ T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor The Buie Co., Inc License No. _____

Address P. O. Box 835 Wichita, Kansas 67201-0835

2-5-85

RECEIVED
STATE CORPORATION COMMISSION

STATE OF _____ COUNTY OF _____, ss.

(employee of operator) or 1985

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ralph Stalcup

(Address) 3511-23 GREAT BEND KS. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of February, 1985

NOTARY PUBLIC - State of Kansas
AMY PATTERSON
My Appt. Exp. 1/17/87

Amy Patterson
Notary Public

My Commission expires: _____


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ROBT. K. LINDSLEY, et al
Farm- Drach No 1

SEC. 11 T. 22 R. 13W
C W/2 SW SE

Total Depth. 3758
Comm 4-8-53 Comp. 4-23-53
Shot or Treated.
Contractor. Lindsley Drilling Co.
Issued. 9-25-54

County Stafford
KANSAS



CASING:

8 5/8 @ 259' w/ 225 sx cmt.
5 1/2 @ 3748.5' w/ 150 sx cmt.

Elevation. 1891

Production. 87 BO, no water

Figures indicate Bottom of Formations.

surface sand & clay	80
shale & shells	380
red bed & sand	820
shale & shells	1250
salt	1445
shale & sandy lime	1535
shale & shells	1725
shale	1750
lime	1960
lime & shale	2070
lime	2220
lime & shale	2290
shale & shells	2730
lime & shale	3045
lime	3250
lime & shale	3395
lime	3503
KC lime	3538
lime	3647
Viola	3673
Viola chert	3690
Simpson shale	3747
Arbuckle	3758
Total Depth	

SCOUT TOPS:

Lansing	3374
Cherty conglomerate	3614
Viola	3638
Simpson	3690
Arbuckle	3747

DST #1: 3395-3477, open 1 hr. 15 min.
rec. 895' gas, 485' HO&GCM, 180' muddy
gaseous oil, fluid rise 665' FP 165-270#
BHP 900#

DST #2: 3488-3503, open 1 hr. 15 min.
fair blow, rec. 30' HO&GCM, 26' specked
O&GCM, 58' SW, BHP 0#

DST #3: 3508-62, open 1 hr. strong
blow thruout. rec. 90' HO&GCM, 240'
oil & mud-GC, 120' oil & gas, BHP
1115#/SI 15 min.

DST #4: 3641-73, open 1 hr. very weak
blow for 21 min. then quit. rec 75'
drilling mud, BHP 0#/Si 15 min.

RECEIVED
STATE CORPORATION COMMISSION

198101975

CONSERVATION DIVISION
Wichita, Kansas