

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above Section Plat

Stafford County, Sec. 11 Twp. 22 Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SW NW NE  
Lease Owner Musgrove Petroleum Corporation  
Lease Name HULLMAN B #2 Well No. 2  
Office Address 518 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed August 7, 19 56  
Application for plugging filed verbally - August 6, 19 56  
Application for plugging approved verbally - August 6, 19 56  
Plugging commenced August 7, 19 56  
Plugging completed August 7, 19 56  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3790 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 210'  
Set 1st plug at 210' w/1 sk hulls & 20 sx cement  
Filled hole with heavy mud to 35'.  
Set 2nd plug at 35' w/1 sk hulls & 10 sx cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick  
I, Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas. (Address)

SUBSCRIBED AND SWORN to before me this 13th day of August, 19 56

R. M. Brundage  
STATE CORPORATION COMMISSION Notary Public.

My commission expires June 16, 1956

24-7368-6 3-53-20M

AUG 15 1956 8-15-56

PLUGGING  
FILE SEC 11 T 22 R 13W  
BOOK PAGE 88 LINE 8

CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: HULLMAN B #2  
 LOCATION: SW NW NE Sec. 11-22-13  
 Stafford County, Kansas  
 COMMENCED: July 27, 1956  
 COMPLETED: August 7, 1956

0	40	Surface soil & sand
40	100	Sand & shale
100	260	Shale & shells
260	280	Lime shells
380	1055	Shale & red bed
1055	1124	Shale
1124	1160	Anhydrite
1160	1580	Shale & shells
1580	1766	Shale & lime streaks
1766	3130	Shale & lime
3130	3250	Lime
3250	3345	Shale
3345	3603	Lime
3603	3700	Cherty lime
3700	3745	Lime & chert
3745	3780	Lime & shale
3780	3790	Cherty lime
	3790	Rotary Total Depth

Set 8-5/8" surface pipe at 285' with 250 sacks cement.

DRY & ABANDONED.

ELEVATION:	1888' K. B.	Brown Lime	3359'	(-1771)
TOPS:		Lansing	3377'	(-1489)
Heebner	3226' (-1338)	Cherty Congl.	3659'	(-1771)
Toronto	3248' (-1360)	Viola	3773'	(-1885)
Douglas	3263' (-1375)	Simpson	3780'	(-1892)

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the HULLMAN B #2, SW NW NE of Section 11-22-13, Stafford County, Kansas, as reflected by the files of Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY Gordon L. Koelling  
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 13th day of August, 1956.

Paul Louis Wolfe  
 Notary Public

My commission expires June 16, 1959.

**PLUGGING**  
 FILE SEC. 11 T. 22 R. 13W  
 BOOK PAGE 88 LINE 8