


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

STAFFORD County. Sec. 11 Twp. 22 Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner SANTA FE PIPE & SUPPLY
Lease Name HULLMAN Well No. 1
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed JUNE 11 19 51
Application for plugging filed 19
Application for plugging approved SEPTEMBER 1 19 61
Plugging commenced SEPTEMBER 1 19 61
Plugging completed SEPTEMBER 5 19 61
Reason for abandonment of well or producing formation DEPLETED



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3727' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	315'	NONE
				5 1/2	3724'	1416'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3727'	-	3697'	5 SACKS CEMENT
3697'	-	300'	MUD
300'	-	290'	ROCK BRIDGE
290'	-	230'	20 SACKS CEMENT
230'	-	35'	MUD
35'	-	BASE	ROCK BRIDGE AND 10 SACKS CEMENT

STATE CORPORATION COMMISSION
WICHITA, KANSAS
12-8-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GLENN & SMITH PIPE PULLING COMPANY
Address P. O. BOX 114 - ELLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*
Box 562, Great Bend
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of OCTOBER 19 61

My commission expires May 19 1962
[Signature] Notary Public.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - PLAINS EXPLORATION CO.
Farm: Hillman No. 1

SEC. 11 T. 22 R. 137
NW NW NW

Total Depth. 3727
Comm. 5-4-51 Comp. 6-11-51
Shot or Treated.
Contractor. Sterling Drlg. Co.
Issued. 9-22-51

County. Stafford
KANSAS



Elevation. 1885

Production. Swab. 2 BOPH NW

CASING:

8 5/8" 315' cem. w/200 sx
5 1/2" 3724' cem. w/50 sx

Figures Indicate Bottom of Formations.

bottom of cellar	10
sand	70
shale & shells	250
red bed	560
shale	730
anhydrite	760
shale	1130
shale & shells	1480
shale & lime	1650
lime	1915
shale	1955
shale & lime	2150
lime	2220
shale & lime	2480
shale	2625
shale & shells	2775
shale	2840
lime broken	2980
lime	3220
lime & shale	3380
lime	3605
shale	3630
lime	3655
chert	3671
shale	3695
chert & shale	3723
lime	3727 RTD
Total Depth	

Tops:	
Anhydrite	730
Heobner	3214
Kansas City	3370
Ch. Congl.	3622
Viola	3630
Simpson	3671
Arbuckle	3723

DST: tool open 1 hr. from
3435' to 3450' 540' salt wtr.
1220# B.H.P.
3723-27' dolomite, fair poro.
good saturation. Good show of
free oil. Good odor.

All measurements carried from
Kelly Bushing. Kelly Bushing
7' above top of Braden Head.

RECEIVED
STATE OF KANSAS
COMMISSION

DEC 6

CONSERVATION DIVISION
WIC