

STATE OF KANSAS
STATE CORPORATION COMMISSION
115 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-185-21,352-0000

LEASE NAME Witt

WELL NUMBER 1

1260 Ft. from S Section Line

560 Ft. from ^W Section Line

SEC. 11 TWP. 22S RGE. 13 (E) of (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 4-5-99

Plugging Completed 4-7-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Globe Operating, Inc.

ADDRESS P.O. Box 12 Great Bend, Kansas 67530

PHONE (316) 792-7607 OPERATORS LICENSE NO. 6170

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	300'	None
				4-1/2"	3800'	2620'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3350' and 4 sks. cement. Shot pipe loose @ 2620'. Pumped 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, released 8-5/8" plug and 100 sks. cement. 60/40 pos. 6% gel. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Globe Operating, Inc.

State of Kansas County of Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

The above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

STATE CORPORATION COMMISSION SUBSCRIBED AND SWORN TO before me this 9th day of April, 1999

APR 12 1999

James Herzberg
Notary Public

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: _____



Form CP
Revised 05-