

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.185.30311-0000

LEASE NAME Hullman

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 10 TWP. 22s RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 4-7-97

Plugging Completed 4-15-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR Stalcup Oil Company

ADDRESS 3224 N. Main, #9 Great Bend, KS 67530

PHONE#(316) 793-3118 OPERATORS LICENSE NO. 7702

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3835'

Show depth and thickness of all water, oil and gas formations. 4-25-97

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	283'	none
				5 1/2	3834'	1900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.
Sanded bottom to 3390' & ran 5 sks cement. Shot at 2700', 2400', 2200', 2000', & 1900'.
Worked pipe loose at 1900'. Pulled up to 800', pumped 10 sks gel. Pulled to 600', pumped
50 sks cement w/100# hulls. Pulled up to 300', pumped 100 sks cement & circulated to surface.
Pulled rest of pipe. Topped off with 25 sks. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Stalcup Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fac-
statements, and matters herein contained and the log of the above-described well as filed t
the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of April, 19 97

Deane Hensberg
Notary Public

My Commission Expires:

