


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 10 Twp. 22 Rge. 13 (E) (W) x

Location as "NE/CNW/SW" or footage from lines SE NE SE  
Lease Owner Sooner Pipe & Supply Co.  
Lease Name Soeken A Well No. #1  
Office Address 301 Petroleum Club Bldg., Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 5-9-67 19  
Application for plugging approved 19  
Plugging commenced 8-1-67 19  
Plugging completed 8-4-67 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Depth to top Bottom Total Depth of Well 3900' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3850'	3121.13'
				8 5/8"	207'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3650', mixed and ran 4 sacks cement thru dump bailer. Mudded hole to 205', set 10' rock bridge. Mixed and ran 3 sacks cement thru dump bailer. Bailed hole dry. Mixed and ran 5 sacks cement thru dump bailer. Filled hole with 2 3/4 yards ready mix from 170' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 4 day of August, 19 67

My commission expires October 1968

Sidney D. Miller  
Notary Public.



WELL LOG

Date Commenced: March 11, 1964  
 Date Completed: June 30, 1964

Soeken A-#1  
 SE NE SE  
 Sec. 10-22S-13N  
 Stafford County, Kansas

0	-	195'	Sand & Clay
195'	-	684'	Red Bed
684'	-	712'	Anhydrite
715'	-	1537'	Shale, Salt, Shells
1537'	-	2826'	Shale, Lime
2826'	-	2860'	Shale
2860'	-	3242'	Lime
3242'	-	3288'	Shale & Lime
3288'	-	3372'	Shale
3372'	-	3617'	Lime
3617'	-	3671'	Lime, Shale
3671'	-	3726'	Lime, Chert
3726'	-	3776'	Lime, Shale
3775'	-	3900'	Dolomite, Lime

ELEVATION: 1891' K.B.

## Formation Data:

Anhydrite	684'
Heebner	3242'
B. Lime	3371'
Lansing	3387'
Conglomerate	3668'
Viola	3682'
Simpson	3725'
Arbuckle	3775'
RTD	3900'

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 7 1967

CONSERVATION DIVISION  
 Wichita, Kansas

Surface Casing: 8 5/8" @ 207' with 250  
 sacks cement

Production Casing: 4 1/2" @ 3850 with 100  
 sacks cement

STATE OF OKLAHOMA  
 COUNTY OF TULSA )ss.

R. B. Hammond, of lawful age, does swear that the facts and statements herein contained are true and correct to the best of his knowledge.

*Ralph B. Hammond*  
 Ralph B. Hammond

Subscribed and sworn to before me this 6<sup>th</sup> day of July 1967

My Commission Expires FEB. 6. 1971

*Linda A. Rychel*  
 Linda A. Rychel NOTARY PUBLIC