

B

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3  
REV. 6-1-68  
STATE CORPORATION COMMISSION

MAR 16 1977  
3-16-77  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -185 -02065-0000 (of this well)

Operator's Full Name Energy Reserves Group, Inc  
Complete Address 1022 Hoover Great Bend, Kansas  
Lease Name Spagemberg A Well No. 3  
Location NW SW SW Sec. 29 Twp. 22 Rge. 11 (E) (W) X  
County Stafford Total Depth 3570  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling  
Address Box 176 Chase, Kansas License No. 683  
Operation Completed: Hour 2:15 pm Day 14 Month March Year 1977

The above well was plugged as follows:

247' of 13' surface cemented with 225 sks, 3542' of 6" long string cemented with 200 sks, sand back to 3492, 2' sk cement with bailer, Recovered 1615' of 6", Spotted 20 sks Gel. 3 sks Hull, 10 sk Gel. through 6" at 615' Pulled Pipe to 220', Spotted 100 sks Cement through pipe, Pulled Remaining pipe filled Surface pipe with 50 sks Cement

Pumped by Sun Cementing Co

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. H. [Signature]  
Well Plugging Supervisor

DATE 3-16-77  
INV. NO. 4805-W