

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

7-24-67

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202Well Plugging Authority,  
issued July 10, 1967.RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Pan American Petroleum

Complete Address P. O. Box 432, Liberal, Kansas 67901

Lease Name P. R. Spangenberg Well No. # 4

Location SW NW SW Sec. 29 Twp. 22 Rge. 11 (E) (W) W

County Stafford Total Depth 3585'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:15 P.M Day 22nd Month July Year 1967

The above well was plugged as follows:

223' of 13 3/8" surface pipe, cemented with 225 sacks. 3558' of 6" long string,  
cemented with 200 sacks. This is an open hole. Bottom of the hole was sanded to  
3500', and cemented with 6 sacks, through the dump bailer, cement from 3500' to  
3460'. 1684' of 6" long string was recovered from the hole. Bridge plug was  
pushed in fluid to 220', bridge plug and rock bridge from 220' to 210'. 7 sacks  
of cement was mixed in a barrel, and put on plug at 210', through the dump  
bailer, and let set over-night. Next day hole was bailed dry, and 43 sacks of  
cement was added to the plug with cement from 210' to 145'. Hole was sanded to  
40', rock bridge from 40' to 30', and cemented with 25 sacks to the base of  
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging SupervisorDATE 7/24/67  
INV. NO. 6021-W