

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

*[Handwritten signature]*  
FILE NO. 2-22  
LOCATION NE-SW-SW  
SEC. 29 TWP 22 RGE. 11W

Dry Hole \_\_\_\_\_ Abandoned Oil Well ✓ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 5 Lease Spengenberg "A"

Operator Standard Oil & Gas Co. Address Box 7, Edlinwood, Kans.

Field \_\_\_\_\_ County Stafford

Total Depth 3597 Feet.

Plugging Contractor West Supply Co. Inc.

Plugging Contractor's License No. 14

Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4" @ 240' cwc. 6" O.D @ 3571'  
w/ 200 sv cem. LWP. @ 3415 top perf. @ 3401  
Handed hole to 3395' dumped 5 sv cem.  
Shot off and pulled 6" casing. Filled hole  
with mud to 240' set rock bridge and  
dumped 20 sv cem. mud to 25' rock bridge  
and 10 sv cem. to base of cellar

Warren H. Garner  
District Conservation Agent

Date Oct 9, 1955

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 1955

CONSERVATION DIVISION  
Wichita, Kansas

10-11-55

**PLUGGING**  
FILE SEC. 29 TWP 22 RGE. 11W  
BOOK PAGE 2 LINE 22