

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-079-36075-0000

245 North Water
Wichita, KS 67202

Operator's Full Name Southern States Oil Company

Complete Address Box 1365, Great Bend, Ks. 67530

Lease Name Neufeldt Well No. # 12

Location NW. NE. Sec. 18 Twp. 22-S Rge. 3 (~~East~~) (West)

County Harvey Total Depth 3678'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. # 683

Operation Completed: Hour: 12:45 PM Day: 22 Month: 12 Year: 1980

The above well was plugged as follows:

8 5/8" sur. csg. 525' circ./cemt. 5 1/2" csg. 3670' Perf. 3403'

Sand hole back to 3350', dumped 5 sx. cemt.

Shot & pulled 2501' 5 1/2" csg. Left 1169' csg. in hole.

Allied Cementing Co. Inc. pumped 4 sx. hulls, 10 sx. gel., 175 sx.

50/50 permix cemt. + 2% gel., down 8 5/8" csg.

Pump Press. 300 lbs. S.I.P. 0 lbs.

RECEIVED
STATE CORPORATION COMMISSION

DEC 30 1980

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I hereby certify that the above well was plugged as herein stated,

DATE 1-8-81

INV. NO. 8386-E

Signed: Don Thompson
Conservation Division Agent

12-30-80