

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-1-68

RECEIVED
STATE CORPORATION COMMISSION

AUG - 2 1979

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 079 - 19147 - 0000 (of this well)

Operator's Full Name Southern States Oil Co.

Complete Address Box 1365 Great Bend, Ks. 67530

Lease Name FRIESEN Well No. #4

Location C E/2 NW SE Sec. 18 Twp 22 Rge. 3 (W)

County HARVEY Total Depth 3689'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. #683

Operation Completed: Hour 1:10 P.M. Day 31 Month 7 Year 1979

The above well was plugged as follows:

8 5/8" csg. 510' / 450' sx cent. - circ - 5 1/2" csg. 3514' / 150' sx cent.
P.B.T.D. 3534'; 4" liner 3500' to 3686' / 15' sx cent.
Perf. 3468'; sand pack to 3440' / 5' sx cent.
Shot & pulled 2504' 5 1/2" csg. left 1010' csg. in hole.
Allied Cementing pumped 3' sx bulls, 10' sx gel,
130' sx 50-50 posmix cent 6% gel, down 8 5/8" csg.
Pump Press. 500# S.T.P. 300#

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-3-79

INT. NO. 6494-F

Signed: Don Thompson
Well Plugging Supervisor