

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-009-03241-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 4 Twp. 16 Rge. 12 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NE SW SE


Lease Owner American Petrofina Co. of Texas
Lease Name Polzin C#1 Well No.
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/31/78 19
Plugging completed 10/31/78 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation Depth to top Bottom Total Depth of Well 3313
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	154	none
				5 1/2"	3310	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Pumped 1 sack hulls, 50 sacks cement, 25 sacks gel, 1 sack hulls and 50 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 6 1978

(If additional description is necessary, use BACK of this sheet) 11-06-78

Name of Plugging Contractor KHELSON CASING PULLING
CHASE, KANSAS CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.


(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 78

Margaret Melcher
Notary Public.

My commission expires



FORMATION

REMARKS

FEET OF STRATA

TOTAL DEPTH

WELL LOG - POLZIN "C" #1

Willow

Well Owner - The Palmer Oil Corporation
 Contractor - The Palmer Oil Corporation

Sec. 4-16S-12W
 Location: NE SW SE
 County: Barton County, Kansas
 Elevation: 1861

Commenced: 12/20/46
 Completed: 1/12/47

Casing: 8-5/8" - 154' Cem. 70 sax
 5-1/2" - 3310' " 35 "

Total Depth: 3313 I.P.: 50 Bbls.

Lime & Clay	0	154
Shale & Shells	154	325
Sand, shale, Pyrite	325	730
Shale & Shells	730	778
Anhydrite	778	810
Shale & Shells	810	1225
Salt & Shale	1225	1425
Red Rock & Shells	1425	1440
Lime Brown	1440	1535
Lime & Shale	1535	1620
Lime Broken	1620	1860
Lime	1860	1885
Lime & Shale	1885	2330
Shale & Shells	2330	2500
Shale & Lime	2500	2685
Lime	2685	2725
Sandy Shale	2725	2740
Lime	2740	2970
Lime & Shale, broken	2970	3040
Shale & Lime	3040	3090
Lime	3090	3309
Lime Arbuckle	3309	3313
Total Depth, Heel line measure		3313

Formation Tops:

Heebner	2953
Lansing	3040
Conglomerate	Trace
Arbuckle	3309
Total Depth	3313

I hereby certify that this is a true and correct log of the above-mentioned well.

THE PALMER OIL CORPORATION

J.P. Miller

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public in said County and State, this
8th day of February, 1947.

Bonnie Duvall
 Notary Public

My commission expires 3/21/49.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 18 1978

CONSERVATION DIVISION
 Wichita, Kansas