

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-009-24,499 0850

LEASE NAME JOHN MILLER

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #1

2160 Ft. from S Section Line

1800 Ft. from E Section Line

SEC. 4 TWP. 16S RGE. 12 (X) or (W)

COUNTY Barton

LEASE OPERATOR L. D. Drilling, Inc

ADDRESS RR 1 Box 183 B, Great Bend, Kansas 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 11-25-91

Plugging Commenced 11-25-91

Plugging Completed 11-25-91

The plugging proposal was approved on 11-25-91 (date)

by Marion Schmidt (KCC District Agent's Name)

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
Surface		0	419	8 5/8"	419'	none

RECEIVED
 STATE CORPORATION COMMISSION
 12-19-91
 DEC 19 1991
 RECEIVED DIVISION

Describe in detail the manner in which the well was plugged, indicating where cement or other fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each section.

25 sxs @ 810', 70 sxs @ 480', 40 sxs @ 180', 10 sxs @ 40', 15 sxs in rat hole.
160 sxs 60/40 poz 6% gel 3%cc

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____

Address P. O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis ~~XXXXXXXXXXXXXXXXXXXX~~ (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) L. D. Davis
 L. D. Davis

(Address) RR 1 Box 183 B Great Bend, Ks
 67530

SUBSCRIBED AND SWORN TO before me this 16th day of December, 1991

Bessie M. De Werff
 Bessie De Werff Notary Public

My Commission Expires: 5-20-93



DRILLER'S WELL LOG

COMMENCED: 11-19-91
COMPLETED: 11-25-91

L. D. DRILLING, INC.
John Miller #1
150'S 100'W NE NW SE
Sec. 4-T16S-R12W
Barton County, Kansas

0 - 419 Surface
419 - 1800 Shale W/lime
1800 - 3048 Lime & Shale
3048 - 3316 Shale & Lime
3316 - 3360 Lime
3360 RTD

ELEVATION: 1877' GR 1882' KB

FORMATION DATA: (Sample)

Anhy 805-828
Heebner 2959 (-1077)
Toronto 2976 (-1094)
Douglas 2988 (-1106)
Brown Lime 3045 (-1163)
Lansing K/C 3058 (-1176)
Base K/C 3305 (-1423)
Cong. 3316 (-1434)
RTD 3360 (-1478)

SURFACE CASING:

8 5/8" set @ 419' W/125 sx. 60/40
Pozmix, 6% gel, 3% CC

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{SS}


L. D. DAVIS, of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

L. D. Davis
L. D. Davis

Subscribed and sworn to before me this 16th day of December, 1991

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-93



RECEIVED
STATE COMPLETION COMMISSION

DEC 19 1991

Geological Survey
Washington, D.C.