


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-009-22573-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 4 Twp. 16S Rge. 12 XX/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
130' W of C NE SW
Lease Owner Petroleum Energy, Inc.
Lease Name Miller "C" Well No. #1
Office Address 710 One Twenty Bldg. Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole.



Locate well correctly on above
Section Plat

Date Well completed 11-24 1981
Application for plugging filed 11-24 1981
Application for plugging approved 11-24 1981
Plugging commenced 11-24 1981
Plugging completed 11-24 1981
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3367'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	258'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 720', 70 sx. cement.
Mud to 240', 40 sx. cement.
Mud to 40', 10 sx. cement.
10 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas Suite 500 Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
401 E. Douglas #500 Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of December, 1981

My commission expires

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Expires Sept. 5, 1984

[Signature]
Carolyn J. Tjaden - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1981
12-10-81
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

OPERATOR: Petroleum Energy, Inc. 710 One Twenty Bldg. Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Miller "C" Well No. #1

Sec. 4 T. 16S R. 12W Spot. 130' W of C NE SW

County Barton State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 258' with 175 Sxs. 2%gel
3%cc

Production: _____ @ _____ with _____ Sxs.

Type Well: D & A Total Depth 3367'

Drilling Commenced: 11-18-81 Drilling Completed 11-24-81

Formation	From	To	Tops
Cellar	0	7	Douglas 3012
Shale, Sand	7	1237	Lansing 3069
Shale, Lime	1237	1933	
Lime, Shale	1933	2135	
Shale, Lime	2135	2390	
Lime, Shale	2390	2600	
Lime	2600	3012	
Shale	3012	3069	
Lime	3069	3328	
Lime, Conglomerate	3328	3367	

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log _____

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 10 1981
 CONSERVATION DIVISION
 Wichita, Kansas

Type and Depths Covered _____