


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-009-22289-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County. Sec. 4 Twp. 16 Rge. 12W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW NW SW  
Lease Owner Petroleum Energy, Inc.  
Lease Name Miller "B" Well No. 1  
Office Address 710 One Twenty Bldg., Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed 3/30 19 81  
Application for plugging filed 3/30 19 81  
Application for plugging approved 3/30 19 81  
Plugging commenced 3/30 19 81  
Plugging completed 3/30 19 81

Reason for abandonment of well or producing formation dry hole  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3360'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	270'	8-5/8"	270'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole full hvy. mud to 500'  
w/ 50 sks 50/50 poz., 4% gel,  
3% c.c., thru DP, Mud to 265'  
w/30 sks thru DP, Mud to 40'  
w/ 1/2 sks hulls, plug & 10  
sks.; filled rathole w/ cement.  
Comp. 2:00 PM, 3/30/81

RECEIVED  
STATE CORPORATION COMMISSION

04-06-81


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company, Great Bend, WKS

STATE OF KANSAS COUNTY OF BARTON, ss.  
Larry Curtis (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Larry Curtis  
P.O. Box 1389, Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of April, 19 81



Ruth Brack  
Notary Public.

My commission expires \_\_\_\_\_

DRILLER'S WELL LOG

DATE COMMENCED: 03/23/81  
 DATE COMPLETED: 03/30/81

Petroleum Energy, Inc.  
 MILLER "B" No. 1  
 SW NW SW  
 Sec. 4, Twp. 16S, Rge. 12W,  
 Barton County, Kansas

ELEVATION: 1876' G.L.  
 1871' K.B.

FORMATION DATA:

793 - 829' Anhydrite  
 2641 - 2686' Lime  
 2686 - 2968' Lime  
 2968 - 2985' Shale  
 2985 - 2998' Lime  
 2998 - 3054' Shale  
 3054 - 3066' Lime, Shale  
 3066 - 3360' Lime  
 3360' RTD

Anhydrite 793'  
 Howard 2641'  
 Topeka 2686'  
 Heebner 2968'  
 Toronto 2985'  
 Douglas 2998'  
 Brown Lime 3054'  
 Lansing KC 3066'  
 RTD 3360'

SURFACE DATA:

Ran 7 jts. used 24# 8-5/8" casing; tally: 262.94'; set @ 270' w/ 140 sks 60/40 poz., 2% gel, 3% c.c., cement. circulated, 3/23/81; By Allied.

PLUGGING DATA:

Hole full hvy mud to 500' w/ 50 sks 50/50 poz., 4% gel, 3% c.c. thru d.p., Mud to 265' w/ 30 sks thru d.p., Mud to 40' w/ 1/2 sk hulls, plug & 10 sks.; filled rathole w/ cement. Comp. 2:00 PM, 3/30/81

A F F I D A V I T

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss.

RECEIVED  
 STATE CORPORATION COMMISSION

APR 6 1981

Larry Curtis , of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and Sworn to before me this 6th day of April, 1981.



Ruth Brack  
 Notary Public