

STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-009-05931-0000  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County, Sec. 4 Twp. 16 Rge. 12 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NE SW

Lease Owner Bennett & Roberts Oil Operations

Lease Name Polzin Well No. 1

Office Address Russell, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2/21 19 57

Application for plugging filed 2/20 verbally 19 57

Application for plugging approved 2/20 verbally 19 57


Plugging commenced 2/21 19 57

Plugging completed 2/21 19 57

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3410 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	212'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

8' wood plug @ 285', 1 rock bridge & 45 sx cement. #2 plug 20' & 5 sx cement to bottom of cellar.

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

Address \_\_\_\_\_

02-27-57  
FEB 2

STATE OF KANSAS, COUNTY OF RUSSELL, ss. Harold Wurst (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst

Russell, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 19 57

Clara Hummel  
Notary Public.

My commission expires 6/17/58

PLUGGING  
FILE SEC 4 T 16 R 12W  
BOOK PAGE 143 LINE 13

Bennett & Roberts Oil Operations  
Polzin #1

NW NE SW Sec. 4-16-12  
Barton County, Kansas

R.T.D. 3410

Casing Record  
8 5/8 Set @ 212' w/125 sx cmt.

Commenced 2/11/57  
Completed 2/21/57

Contractor: Bennett & Roberts Drilling, Inc.

Surface soil & clay	10
Post Rock	70
Shale	125
Sandy Shale	195
Shale	550
Shale & Red Bed	812
Anhydrite	843
Shale, Red Bed & Shells	1235
Shale & Shells	1455
Shale, Shells & Lime Streaks	1550
Shale & Lime	3149
Lime	3332
Cherty Cong.	3375
Lime	3410

STATE OF KANSAS)  
RUSSELL COUNTY ) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By John R. Lavin

Subscribed and sworn to before me this 26th day of February, 1957.

Clara Hammond  
Notary Public

My Commission Expires 6/17/58

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 4 T. 16 R. 2 W  
BOOK PAGE 143 LINE 13