


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 29 Twp. 22 Rge. (E) 11 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$ NW $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Mr. Simon Lebow
Lease Name Waite Well No. 1
Office Address 608 Oil Capital Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 24 19 51
Application for plugging filed April 24 19 51
Application for plugging approved April 24 19 51
Plugging commenced April 24 19 51
Plugging completed April 24 19 51
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. F. Stough
Producing formation Depth to top Bottom Total Depth of Well 3670 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	260'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 250'.
Set plug at 250' and filled with 15 sacks of cement.
Filled hole with heavy mud to 30' and set plug at 30'.
Filled with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1951

5-1-51

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Mr. Simon Lebow Wichita, Kansas
Address 608 Oil Capital Building
Tulsa 3, Oklahoma

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON J. KOELLING (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon J. Koelling
407 K.F.H. Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of April, 19 51

Margie J. Jirel
Notary Public.

My commission expires December 5, 1951

PLUGGING
FILE SEC 29 T 22 R 11 W
BOOK PAGE 78 LINE Y

CONTRACTOR'S WELL LOG

COMPANY: Mr. Simon Lebow
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: Waite No. 1
 LOCATION: NE/4 NW/4 SE/4, Sec. 29-T22S-R11W,
 Stafford County, Kansas.
 COMMENCED: 4/13/51
 COMPLETED: 4/24/51

0	40	Surface soil and clay
40	175	Sand and gravel
175	250	Red bed, sand and shale
250	260	Red bed
260	620	Red bed and shale
620	1230	Shale and shells
1230	1415	Salt, shale and shells
1415	3398	Lime and shale
3398	3460	Cherty lime
3460	3520	Lime
3520	3580	Lime and shale
3580	3600	Cherty lime
3600	3645	Lime and shale
3645	3670	Rotary Total Depth

Set 260' of 8-5/8" surface casing, cemented with 200 sacks.
 Dry and Abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Waite #1, Sec. 29-22S-11W, Stafford County, Kansas, as reflected by files of the Musgrove Petroleum Corporation. RECEIVED STATE CORPORATION COMMISSION

MUSGROVE PETROLEUM CORPORATION 1951
 CONSERVATION DIVISION
 Wichita, Kansas
 By Gordon L. Koelling
 Secretary

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas this 26th day of April, 1951.

Madeline J. Jurek
 Notary Public

My commission expires: 12/5/51

