

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24187-00-00
Spot: E2NENWSE Sec/Twnshp/Rge: 22-10S-17W
2310 feet from S Section Line, 1465 feet from E Section Line
Lease Name: BICE Well #: 1
County: ROOKS Total Vertical Depth: 3750 feet

Operator License No.: 4787
Op Name: TDL, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3745		305 SX
SURF	8.625	223		160 SX
TI	2.875	3686		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2017 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BRETT HILDERBRAND Company: TDL, INC. DBA Phone: (785) 871-7311

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 13 sx gel (100 # bags) and 700 # hulls.
DV Tool at 1287' w/155 sx cement.
Production perforations: 3347' - 3443'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2017 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3293' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1304' and pumped 150 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/35 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 200 psi immediately.

GPS: 39.16791N -099.20106W

Perfs:

Top	Bot	Thru	Comments
3439	3443		
3420	3422		
3395	3397		
3347	3350		

KCC WICHITA
MAY 02 2017
RECEIVED

INVOICED
MAY 11 2017

Remarks: GLOBAL CEMENTING TICKET # 2905

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

cm

APR 19 2017