

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26123-00-00
Spot: E2W2E2SW Sec/Twnshp/Rge: 7-14S-18W
1320 feet from S Section Line, 1855 feet from W Section Line
Lease Name: HIATT Well #: 1
County: ELLIS Total Vertical Depth: 3899 feet

Operator License No.: 4787
Op Name: TDL, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3898		150 SX
SURF	8.625	234		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2017 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: BRETT HILDERBRAND Company: TDL, INC. DBA Phone: (785) 871-7311

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 600 # hulls and 17 sx gel.
DV Tool at 1442'.
PBTD: 3802'.
Perforations: 3490' - 3658' LKC.
Operator elected to run tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2017 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express ran in hole to 3423' with tubing. Quality rigged to tubing and pumped 8 bbl water followed by 17 sx gel and 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1500' and pumped 150 sx cement w/350 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2' casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" surface casing with a swedge and pumped 10 sx cement with 200 psi. Shut in pressure 200 psi.

GPS: 38.84548 -099.36707

Perfs:

Top	Bot	Thru	Comments
3788	3802		
3654	3658		
3639	3643		
3623	3625		
3490	3658		
2490	2492		

KCC WICHITA
MAY 02 2017
RECEIVED

INVOICED
MAY 11 2017

Remarks: QUALITY OIL WELL CEMENTING CO TICKET # 208

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CJA