

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-20844-00-00  
Spot: SWNE Sec/Twnshp/Rge: 35-27S-19W  
3295 feet from S Section Line, 2246 feet from E Section Line  
Lease Name: ASHLEY Well #: 2  
County: KIOWA Total Vertical Depth: 4847 feet

Operator License No.: 5118  
Op Name: TGT PETROLEUM CORPORATION  
Address: 7570 W 21ST ST N BLDG 1046A  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4700		WITH 2 SX CMT
PROD	5.5	4844	1676	WITH 250 SX CMT
SURF	8.625	418		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2017 3:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Revd. from: SPENCER SIROKY Company: FOSSIL DRILLING Phone: (316) 773-2266

Proposed Plugging Method: CIBP @ 4700' WITH 2 SX CMT. PLUG AT 1260' WITH 12 SX GEL & 50 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/20/2017 6:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT. 1ST PLUG AT 1268' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4780	4784		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

SA

(TECHNICIAN)

RECEIVED  
APR 21 2017  
KCC DODGE CITY

INVOICED  
MAY 11 2017