

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02071-00-00
Spot: CSWNWNW Sec/Twnshp/Rge: 29-22S-11W
1650 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: SPANGENBERG W Well Number: 4
County: STAFFORD Total Vertical Depth: 3578 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: PO BOX 780
MIDDLEBURG, VA 20118

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 13.375 feet: 228 WITH 225 SX CMT
Production: Size 6 feet: 3578 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/18/2001 2:00 PM

Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC

Proposal Rcvd. from: BENNY GRIFFIN Company: LAVETAL OIL & GAS Phone: (540) 687-8219

Proposed Plugging Method: BRIDGE PLUG SAND 50' ABOVE PERFS & 6 SX CMT. 1ST PLUG AT 660' WITH 20 SX GEL & 90 SX CMT. 2ND PLUG AT 250' WITH 90 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 10/18/2001 5:45 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3550'. PERFS AT 3579-3622'. SANDED TO 2900' & 6 SX CMT ON TOP OF SAND WITH A DUMP BAILER. SPOTTED PLUGS THROUGH CASING 1ST PLUG AT 660' WITH 20 SX GEL - 90 SX CMT. 2ND PLUG AT 250' WITH 90 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 670' OF 6" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey

RECEIVED

OCT 22 2001

KCC WICHITA

(TECHNICIAN)

INVOICED OCT 19 2001

DATE 10-22-01

INV. NO. 2002060831

Form CP 201