

1 070043

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW NE NE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,295-0000  
SEC. 29, T 22 S, R 11 W/E  
4950 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5407  
Operator: Hupfer Oil & Gas  
Name & Address: 3711 Country Lane  
Hays, KS 67601

Lease Name Gatton Well # C-2  
County Stafford  
Well Total Depth 3700' Arbuckle 62' <sup>20.25</sup> feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30, Inc. License Number 5107  
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 29 Month: October Year: 19 85

Plugging proposal received from E. J. Woody

(company name) H-30 (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1824  
Anhydrite 1451'

1st plug at 3700' with 50 sx cement

2nd plug at 1630' with 50 sx cement

3rd plug at 350' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 5  
sx cement. Plugging Proposal Received by Dan Goodrow

Plugged water well with 5 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 8:00 pm Day: 29 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3700' with 50 sx cement, 2nd plug at 1630' with 50

sx cement, 3rd plug at 350' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement, 7th plug to circulate mouse hole with 5 sx cement, and plugged water well

with 5 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton  
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

STATE CORPORATION COMMISSION

Signed

Dan Goodrow  
(TECHNICIAN)

DATE NOV 4 1985

NOV 1 1985 11-1-85

INV. NO. 10881 10-29

15-185-22295-0000

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: October 5 1985  
month day year

API Number 15- 185-22,295 Yes

OPERATOR: License # 5407  
Name Hupfer Oil & Gas  
Address 3711 Country Lane  
City/State/Zip Hays, Kansas 67601  
Contact Person Dennis D. Hupfer  
Phone (913) 628-8666

NW NE NE Sec 29 Twp 22 S. Rge 11  
(location)  
4950 Ft North from Southeast Corner of Section  
990 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107  
Name H-30, Inc.  
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 330 feet.  
County Stafford  
Lease Name Gatton Well# C-2  
Domestic well within 330 feet: yes  no  
Municipal well within one mile: yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 250 ~ 100 feet  
Lowest usable water formation Dakota  
Depth to Bottom of usable water 250 feet  
Surface pipe by Alternate:  1  2  
Surface pipe to be set 300 feet  
Conductor pipe if any required N/A feet  
Ground surface elevation 1824 feet MSL  
This Authorization Expires 3-24-86  
Approved By [Signature] 9-24-85

If OWWO: old well info as follows:  
Operator \_\_\_\_\_  
Well Name \_\_\_\_\_  
Comp Date \_\_\_\_\_ Old Total Depth \_\_\_\_\_  
Projected Total Depth 3650 feet  
Projected Formation at ID Arbuckle  
Expected Producing Formations Arbuckle/Lansing

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.O.C. specifications.  
Date Sept. 23 Signature of Operator or Agent [Signature] Title resident  
Form C-1 4/84

10-21-85 - 8 5/8" - 300'

Kelly

(over)

PUSHER E. J. Wordy  
TD 3700' FORMATION Arbuckle 62ft. into  
SURFACE PIPE 8 5/8" @ 324  
ANHYDRITE 1451 ELEVATION 1824  
STARTING TIME & DATE 1:00 PM 10-29-85  
COMPLETION TIME & DATE 10/29/85 - 8:00 PM  
1st PLUG @ 3700' FT. W/ 50 SX  
2nd PLUG @ 1630 FT. W/ 50 SX  
3rd PLUG @ 350 FT. W/ 50 SX  
4th PLUG @ 40 FT. W/ 10 SX  
RAT HOLE CIRCULATION W/ 10 SX  
MOUSE HOLE CIRCULATION W/ 5 SX  
WATER SUPPLY WELL PLUGGED W/ 5 SX

TECHNICIAN D.G. Halliburton  
60/40 p.p. 670 gal

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1985  
CONSERVATION DIVISION  
Wichita, Kansas