

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

10-3
2-100749
167
R
RECEIVED
KANSAS CORPORATION COMMISSION

OCT 29 1991

API NUMBER: 15-079-00848-0001 CONSERVATION DIVISION
SE NE NE, SECTION 18 TOWNSHIP 22 WICHITA, KS
RANGE 35

OPERATOR LICENSE # 5430 4290 FEET FROM S SECTION LINE
360 FEET FROM E SECTION LINE

OPERATOR Energy Three, Inc.

NAME & P. O. Box 1505

ADDRESS Great Bend, KS 67530

LEASE NAME: Neufeld #9

COUNTY: Harvey

WELL TOTAL DEPTH: 3566' 115.89

PIPE: 4-1/2" @ 3550'/100 sx

SURFACE CASING: 13-3/8" @ 315'

SURFACE CASING: 8-5/8" @ 3170'

ABANDONED OIL WELL X GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: Perf 3404-18', 3436-40', 3448-50'

PLUGGING CONTRACTOR: Kelso Casing Pulling, Inc.

ADDRESS: Box 347, Chase, KS 67524

LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 10:00a DAY: 3 MONTH: 10 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Manny

COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Pump 500# hulls, 20 sx gel, 100 sx cmt, 2 sx gel, 250
sx cmt thru swedge, leaving 100' cmt plug from 350' to
250' & 250' cmt plug at top - (on 10/1/91 gave 5 hulls,
20 gel, 350 sx cmt) - bottom plug, sand to 3350' & 4 sx
cmt w/bailer - shoot & pull pipe.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 11:00a DAY: 3 MONTH: 10 YEAR: 1991

ACTUAL PLUGGING REPORT:

Sanded to 3350' & dumped 4 sx cmt w/bailer - shot &
pulled 2512' of 4-1/2" - no 8-5/8" found in well -
hooked up to welded 13-3/8" & pumped 500# hulls, 20 sx
gel, 100 sx cmt, 2 sx gel, 250 sx cmt - shut in well.

REMARKS: Allied #3353 500# oper PSI - SI 100#

INVOICED
DID OBSERVE THIS PLUGGING.

DATE 11-8-91

INV. NO. 33665

John Sanders
John Sanders (AGENT)

FORM CP-2/3
REV. 3/90