

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

10-18

2-100751 359

API NUMBER: 15-079-19145-0000

NW NE SE, SECTION 18 TOWNSHIP 22 RANGE 3W

OPERATOR LICENSE # 5430

2530 FEET FROM S SECTION LINE

990 FEET FROM E SECTION LINE

OPERATOR Energy Three, Inc.

NAME & P. O. Box 1505

ADDRESS Great Bend, KS 67530

LEASE NAME: Neufeld #4

COUNTY: Harvey

WELL TOTAL DEPTH: 3454'

CONDUCTOR PIPE: 5-1/2" @ 3475'/150 SX

SURFACE CASING: 8-5/8" @ 505'/325 SX

ABANDONED OIL WELL X GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: Perf 3421-47'

PLUGGING CONTRACTOR: Kelso Casing Pulling, Inc.

ADDRESS: Box 347, Chase, KS 67524

LICENSE:

COMPANY TO PLUG AT: HOUR: 9:00a DAY: 27 MONTH: 9 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Manny

COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Sand to 33;70' & dump 5 sx cmt - shoot & pull pipe -
squeeze from top 3 hulls, 10 gel & 35 sx cmt gel spacer
- then 115-125 sx cmt, leaving 100' cmt approx 550-450'
and 350' to surface.

PLUGGING PROPOSAL RECEIVED BY: Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 2:00p DAY: 18 MONTH: 10 YEAR: 1991

ACTUAL PLUGGING REPORT:

Sanded to 3360' and dumped 5 sx cmt - shot & pulled
1961' of 5-1/2" - hooked up to swedge & squeezed 500#
hulls, 10 sx gel, 50 sx cmt - nipple broke w/400# PST
on well - it was unsafe to get in cellar - left well
shut in. On 10/18/91 drilled w/4-1/2" bit to 350' -
ran tub to 350' - circ 130 sx cmt to surface.

REMARKS: Allied #3354 & #2654 60/40 6% gel

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 11-15-91

INV. NO. 33736

J. L. Sanders
J. L. Sanders (AGENT)

FORM CP-2/3
REV. 3/90

112.25

11-6-91

RECEIVED

STATE CORPORATION COMMISSION

NOV 6 1991